



SARATOGA COUNTY WATER AUTHORITY

JOHN E. LAWLER, CHAIRMAN
ED HERNANDEZ, P.E., EXECUTIVE DIRECTOR

260 BUTLER ROAD, GANSEVOORT, NY 12831
TELEPHONE: (518) 761-2058
FACSIMILE: (518) 792-4942
www.saratogacountywaterauthority.com

THOMAS K. CUMM
ANITA M. DALY
ARTHUR J. JOHNSON
DARREN O'CONNOR
JAMES M. SMITH
TIM SZCZEPANIAK

Storage Building Project Addendum No.2 November 5, 2018

Please note the following response to questions and clarifications for the Saratoga County Storage Building bid documents:

1. Are the six overhead doors along the length of the building to be electrically operated?
As previously indicated in Addendum #1, there are seven (7) overhead doors. Any references to a total of six shall be disregarded. Overhead doors shall be manual operation and shall include track, all mounting hardware, locks along with lift handles and a manual direct drive chain hoist system as recommended by the manufacturer.
2. The bid form does not have a line to enter a price for alternate #2, please advise. **The bid form has been corrected. A copy is attached.**
3. Will the county remove & re-install the fencing in order to provide access at the rear of the existing generator? **It is the contractor's responsibility to remove and replace the fence if required.**
4. Technical specifications part 2.08 says 'Contractor is responsible for installing conduit for owner's future electrical installation' please specify exactly what work is requires for this. **Contractor shall supply four 2" electrical conduits between the floor slab and below the foundation to 24" beyond the exterior of the building to allow for future installation of electrical. Conduit material and depth shall meet applicable building codes.**
5. Is temporary water and electrical power available on site for the contractor's use? **Contractor shall supply its own temporary water and electrical power.**
6. Will the Owner provide corner offset for the contractor to start his layout from? **Owner will assist Contractor is setting building location.**
7. **The project shall be complete within 7 months of contract award.**